

Klamath Dam Removal - Lessons Learned as a River is Reborn



A Concurrent Session at the 42nd Annual Salmonid Restoration Conference
Santa Cruz, California, April 29 - May 2, 2025

Session Coordinators: Bob Pagliuco, *Marine Habitat Resource Specialist, NOAA Fisheries Restoration Center*; and Mike Belchik Sr. *Water Policy Analyst, Yurok Tribe*



This session will highlight the current state of post-dam removal restoration, dam removal lessons learned, science and monitoring, and what the future holds following implementation of the largest river restoration project in the world.



Free flowing Klamath River post-dam removal.

Photo: Swiftwater Films

Presentations



- **Planning, Implementation, and Lessons Learned for the Removal of the Four-Dam Complex of the Lower Klamath Project**
Mort McMillen, *Executive Vice-President, McMillen Inc.*.....Slide 4
- **From Reservoirs to Rivers: A Look at the Past Year of the Klamath River Renewal Project Restoration Journey**
Dan Chase, *Director, Fisheries, Aquatics & Design – Western Region, RES*.....Slide 87
- **Water Quality Conditions During Klamath Dam Removal Drawdown**
John R. Oberholzer Dent, *Biologist, Karuk Tribe Department of Natural Resources*Slide 132
- **Mapping a New River – First Aerial Surveys of the Klamath River After a Century of Dams**
DJ Bandrowski, P.E., *Senior Civil Engineer/Program Manager; Yurok Tribe*.....Slide 173
- **Factors Limiting Filamentous Algae and Rooted Macrophyte Growth During Dam Removal in the Klamath River**
Isabelle Tang, MS Student, *Oregon State University*.....Slide 199
- **Quantifying Benthic Macroinvertebrate Responses to Klamath Dam Removal During Juvenile Salmonid Outmigration Season**
Rosa Cox, Masters Student, *Cal Poly Humboldt*.....Slide 229
- **Evaluating the Effectiveness of Dam Removal on the Klamath River Using SONAR and Radio Telemetry**
James Whelan, *Project Manager, California Trout* and Alex Corum, *Sr. Fisheries Biologist, Karuk Tribe*.....Slide 268

Planning, Implementation, and Lessons Learned for the Removal of the Four-Dam Complex of the Lower Klamath Project



Agenda

- General Project Overview
- Dam Removal Approach
- Dam Safety Program
- Lessons Learned
- Questions




WARNING

“Presentation by pocket protector wearing introverted old school civil engineer.”



Project Vicinity Map



Project Purpose

Achieve dam removal, a free-flowing condition on the Klamath River, and volitional fish passage.




KRRC Organization Chart— Implementation Phase


NOTES:

(1) OPERATING LKP UNDER AN O&M AGREEMENT WITH THE RENEWEL COORPORATION DURING PRE-DRAWDOWN PERIOD.

(2) THE RENEWAL COORPORATION, PACIFICORP, AND USBR WILL COORDINATE ON OPERATION DURING THE PREDRAWDOWN PERIOD. USBR AND RENEWAL CORPORATION WILL WORK DIRECTLY DURING DRAWDOWN PERIOD



Dam Removal Project Timeline



Pre-Drawdown Year:

- Dam/tunnel modifications
- Road/bridge improvements
- CoY Waterline Replacement
- Fall Creek Hatchery Construction
- Water Quality/Quantity Monitoring
- Copco No. 2 Dam Removal

Drawdown Year:

- Dam and infrastructure removal
- Initial reservoir restoration

Post-Drawdown Years:


- Site Restoration
- Monitoring/Adaptive Management



The background of the slide features three large, dark teal arches that resemble stylized windows or doorways, set against a white background. A horizontal teal band spans across the middle of the image, serving as a backdrop for the title text.

Observations and Lessons Learned

How do you Approach Large Dam Removal?




Review the Original Dam Construction

- Construction drawings
- Construction photos
- Construction manager reports
- Identify original borrow sources, cofferdam and diversion plans, temporary works, and material placement records
- Look for field adjustments during construction – why did they do this?

Main Engineering Considerations for Dam Removal

- Hydrologic and river flow conditions
- Means and methods for lowering reservoirs – low level outlets
- Cofferdam and water diversion requirements
- Construction access
- Means and methods for dam removal
- Dam safety during construction
- Disposal sites
- Site restoration
- Regulatory and permitting requirements – how do you get the dams out AND meet these conditions


Regulatory: 70 + Approvals/Agreements



Upper Klamath Basin

Bureau of Reclamation, Mid Pacific Region Major Storage Reservoirs in the Klamath River Basin

Tue Apr 18 2023 10:32:35 GMT-0700 (Pacific Daylight Time)



— **Flow Management and Operations Coordination**

Pre-Drawdown Period

- Monitor spring runoff to determine timing for initiating Pre-Drawdown construction activities
- Coordinate peaking flow operation at JC Boyle to support whitewater community recreation
- Manage flow releases from Keno and Lower Klamath Reservoir operations to support shutting down Copco No. 1 to remove Copco No. 2 dam, install access, and remove trees from Ward Canyon
- Maintain flows to meet BiOp requirements in Klamath River below Iron Gate Dam

Drawdown Period


- Determine start date for dam removal
- Reduces flow from Keno to support low-level outlet final opening
- Reduces flow from Keno to support final Iron Gate Dam cofferdam breach
- Control flood flows out of Klamath Lake
- Maintain flows to meet BiOp requirements in Klamath River below Iron Gate Dam

J.C. Boyle Dam





JC Boyle original approach channel and spillway low-level conduits under construction.

JC Boyle original approach channel with river bypassed through low-level outlets under the spillway



JC Boyle Reservoir Drawdown & Dam Removal

- 1) JC Boyle reservoir was drawn down in January 2024. Existing culverts underneath the dam (which were used to divert water during original construction) were opened to provide a low-level outlet at the spillway.
- 2) Stoplogs (a thin concrete wall) that were at the upstream end of the diversion culverts were blasted out, allowing the reservoir to drawdown with water passing beneath the existing spillway.



JC Boyle Drawdown



Reservoir drawdown
initiated after blasting the
first diversion culvert.
16 January 2024



JC Boyle Drawdown



JC Boyle reservoir
drawdown complete.
Spillway conduits
fully open.

February 2024



JC Boyle Drawdown



JC Boyle reservoir drawdown complete. Historic cofferdam located in the center of the image. 1200 cfs flushing flow in progress.

24 January 2024



J.C. Boyle Dam Removal



JC Boyle
cofferdam
breach.
30 July 2024



J.C. Boyle Dam Removal



JC Boyle new river
channel through
dam footprint.
29 September 2024



J.C. Boyle Power Canal Removal




JC Boyle power canal
site restoration.
29 September 2024



Pre-Drawdown: Copco Complex




Copco No. 1



Copco No. 2



Lower Klamath Project – Reservoir Operations Schematic



Copco Reservoir – Drawdown Schematic



Copco No. 2 Demolition – Dam



Copco No. 2 Drawdown




Copco 2 dam site before demolition.
13 June 2023




Completed Copco 2 dam site.
23 January 2024

2023 Pre-Drawdown: Copco No. 1 Dam Adit Tunnel

- 1) Green work pad constructed on downstream side at base of dam.
- 2) 10' diameter adit tunnel excavated through base of dam. Plug left in place at upstream end.



- 3) 10' diameter extension pipe installed downstream of tunnel.
- 4) Extension pipe covered with spillway apron earthen material and grouted in place.



2024 Facilities Removal: Copco No. 1

- Concurrent with dam removal, existing structures at the Copco 1 facility will be decommissioned and removed.
- Facilities include the existing hydro-power generation equipment, the powerhouse structure itself, and several other buildings in the vicinity of the dam.



Copco No. 1 – Adit and Forebay Dredging



COPCO 1 LOW LEVEL ADIT



DREDGING IN COPCO 1 FOREBAY

Copco No. 1 - Adit



First section of steel extension
pipe set in place at the Copco 1
low-level adit.

10 October 2023

Copco No. 1 - Adit



General view of Copco 1 dam and powerhouse with progress on grouted riprap placement over the steel extension pipe.
8 November 2023

Copco No. 1 Drawdown



View of Copco No. 1
Powerhouse and river channel
after adit plug blasted.
23 January 2024




Copco No. 1



Reservoir site looking upstream from the new dam site. (Left center) Working on original dam site.



Gauging Station on Klamath River at Copco No. 1, May 1911.



First water turned through Copco No. 1 diversion tunnel, October 12, 1912.



Headworks Copco No. 1 diversion tunnel, October 12, 1912.

Copco No. 1 Dam Removal



Traction line winched excavator removing diversion tunnel gate operator concrete piers at Copco 1.

6 February 2024



Copco No. 1 Drawdown




View of Copco No. 1
Dam and reservoir after
drawdown.

31 January 2024



Copco No. 1 Diversion Tunnel



Copco 1 diversion tunnel
plug loaded and tied in.
1 March 2024



Copco No. 1 Diversion Tunnel



Copco 1 diversion tunnel
after blasting the plug.

1 March 2024



Copco Complex Construction Site



Overview of Copco 1
and 2 sites and the
Klamath River between
Copco 1 and 2.

15 March 2024



Copco No. 1 Dam Removal



Copco No. 1 dam
Phase 4 Blast.
18 June 2024



Copco No. 1 Dam Removal



Copco No. 1 upstream
excavation and
powerhouse backfill.
12 July 2024



Copco No. 1 Dam Removal



Concrete rubble from
Phase 5B blast
partially removed.
9 August 2024



Copco No. 1 Dam Removal



Breaching historic
cofferdam.

28 August 2024



Copco No. 1 Dam Removal



Klamath River flowing
through the dam site.
13 September 2024



Copco No. 1 Dam Removal



Dam removal complete
and site restoration in
progress.

19 September 2024



Iron Gate Dam



View of Iron Gate dam and reservoir before drawdown.
20 December 2023

Iron Gate Dam



Iron Gate Dam diversion
tunnel intake with cofferdam
across Klamath River

Iron Gate Dam diversion
tunnel intake with three
sides of trashracks



— Iron Gate Outlet Tunnel Modifications



Iron Gate Drawdown



Klamath River at Low
Level Outlet tunnel.
5 February 2024



2024 Reservoir Drawdown & Dam Removal: Iron Gate

- Drawdown of Irongate Reservoir used the existing low level outlet diversion tunnel.
- Beginning in May, Large trucks and excavation removed the dam embankment from the top down
- Approximately 1 million cubic yards were excavated in total
- The existing spillway was be filled in with earthen materials
- The powerhouse equipment was removed and the powerhouse demolished
- Once the dam and facilities were removed, a new river channel was built in the dam footprint. Channel grading was completed in October 2024



Iron Gate Construction



Exposed diversion
tunnel intake
structure trash
racks at Iron Gate.
12 March 2024



Iron Gate Drawdown



Iron Gate project site including dam (upper right), haul road (center), and waste disposal area (upper left). Note high water level due to ESA geomorphic releases.
15 March 2024



Iron Gate Dam Removal



Waste Disposal Site.
7 July 2024



Iron Gate Dam Removal



Embankment
removal
progress –
looking
downstream.
12 August 2024



Iron Gate Dam Removal



Waste Disposal Site.
12 August 2024



Iron Gate Dam Removal



Embankment removal
from upstream.
3 September 2024



Iron Gate Dam Removal



Embankment
removal and
spillway fill.
29 September 2024



The background of the slide features three large, dark teal arches that resemble the top of a bridge or a series of stylized hills. These arches are set against a plain white background. A horizontal teal band, matching the color of the arches, spans the width of the slide and is positioned in the middle. The text "Dam Safety Program" is written in white, bold, serif font on this band.

Dam Safety Program

Dam Safety Considerations

- Required developing plans specific to the planned construction activities and dam removal nature of the Lower Klamath Project
- Considered FERC license transfer from the original licensee, PacifiCorp, to the new co-licensee, KRRC, State of CA, and State of OR
- Addressed anticipated operation and dam safety risks during the project implementation phases: Pre-Drawdown, Drawdown, and Post-Drawdown
- Required well-developed plans and implementation by the new licensee to ensure effective public safety throughout the dam removal process

Pre-Drawdown Phase (2023) Plans

- Owners Dam Safety Program (ODSP)
- Dam Safety Surveillance and Monitoring Program (DSSMP)
- Emergency Action Plan
- Public Safety Plan
- Temporary Construction Surveillance Monitoring Plan (TCSMP)
- Temporary Construction Emergency Action Plan (TCEAP)
- Operations and Flow Management Plan
- Slope Stability Monitoring Plan
- Quality Control and Inspection Plan (QCIP)
- Copco No. 2 Final Facility Termination Plan

Drawdown Phase (2024) Plans

- Owners Dam Safety Program (ODSP)
- Dam Safety Surveillance and Monitoring Program (DSSMP)
- Emergency Action Plan
- Public Safety Plan
- Temporary Construction Surveillance Monitoring Plan (TCSMP)
- Temporary Construction Emergency Action Plan (TCEAP)
- Operations and Flow Management Plan
- Slope Stability Monitoring Plan
- Quality Control and Inspection Plan (QCIP)
- Debris Management Plan
- Copco No. 1, Iron Gate, and JC Boyle Final Facility Termination Plan

Pre-Drawdown Phase (2023)

- Plan focused on monitoring activities at Copco No. 1, Copco No. 2, and Iron Gate
- No work activities at JC Boyle
- KRRC contracted O&M of the plants to PacifiCorp during the Pre-Drawdown Period
- Active operation and flow management with PacifiCorp and USBR to support construction
- Completed modifications to Copco No. 1 and Iron Gate to facilitate final drawdown
- Removed Copco No. 2 diversion dam

Drawdown Phase (2024)


- Implemented site-specific Drawdown Phase Dam Safety Surveillance and Monitoring Plan
- Plan focused on monitoring activities at JC Boyle, Copco No. 1, and Iron Gate Dams
- Copco No. 2 dam already removed
- Completed final facility termination at each remaining plant to initiate final drawdown – PacifiCorp no longer providing operation support
- Active operation and flow management with USBR/Agencies/Tribes to support construction
- Active dam removal activities initiated in February 2024 with final dams removed by October 1, 2024.

Copco No. 1 Adit Blasting Monitoring



Copco No. 1 Adit

Blasting Monitoring



Drawdown Phase Primary Monitoring

- JC Boyle Dam embankment stability during reservoir drawdown and dam removal
- Scour Hole slope stability during construction
- Copco Lake Reservoir Rim Slope Stability during Reservoir Cycling
- Copco No. 1 Dam stability during blasting and removal
- Iron Gate reservoir rim slope stability during drawdown
- Iron Gate Dam embankment stability during drawdown
- Iron Gate Tunnel condition during reservoir drawdown

Iron Gate Reservoir Slope Stability Monitoring





Lessons Learned

— **Definition of Lessons Learned**

- “Knowledge or understanding gained from experience”

Pre-Drawdown Phase (2023)

- Copco No. 1 adit blasting approach
- Iron Gate Diversion Tunnel as-built conditions

Drawdown Phase (2024)

- Iron Gate Diversion Tunnel Cavitation
- Copco No. 1 Over Blasting
- Sediment Transport Characteristics

Copco No. 1 Adit Blasting

Issue: Steel rails placed in the original dam concrete placement caused the blast to vary depending on the number and location of the rails. This resulted in a delay in advancing the adit construction as well as high fly rock debris in the first two blasts.

Lesson Learned: Blasting schedule should be developed to accommodate multiple test blasts and “dialing-in” of blasting program to accommodate site specific conditions. Data from the field blasting was required in order to determine the appropriate powder factor to shear off steel rails and reach the full blast depth but stay below a safe threshold for vibration. More fly rock guarding was required than anticipated.

Copco No. 1 Adit Blasting



Picture shows at least 7 pieces of rail at random angles that kept the shot from breaking to full depth.




Sediment Transport Characteristics

Issue: Project planning called for flushing the reservoir sediment out of the dam reservoirs and out to the ocean. Sediment characteristics resulted in variation in sediment movement by reservoir and flow management to optimize the sediment movement.

Lesson Learned: Extensive sediment modeling was used to determine the sediment transport mechanism and volumes moved out of the reservoirs. Maintaining the ability to supplement water flows to help move sediment during critical times was invaluable in meeting the overall sediment flushing and transport objectives of the Lower Klamath Project.

Initial Drawdown Schedule



Sediment Transport Characteristics



Sediment Transport Characteristics



Thank you.



Mort McMillen, PE,
mortmcmillen@mcmillen.com

Copco No. 1 Dam Intake Blasting Overbreak

Issue: Blasting of the penstock intake resulted in significant overbreakage and large of block of concretes impacting and partially damaging the outlet conduit. This resulted in significant work to remove the concrete and restore full diversion pipe flow.

Lesson Learned: Contractor was pushing the schedule using as large of concrete blasts as possible. The penstock intake was set up as a single blast to facilitate a single removal activity. A smaller blast area would have been more appropriate controlling the extent of the concrete removal and overbreakage, protecting the diversion pipe, and minimizing any potential impact to schedule. Lesson learned is that bigger is not always better in the world of blasting.

Copco No. 1 Intake Blasting Overbreak



— Iron Gate Diversion Tunnel Anchors

Issue: Super cavitation blocks were installed at the end of the existing concrete lined section of the diversion tunnel downstream from the gate structure. During installation, placement of the rock anchors tying the baffles to the concrete was delayed due to a void and unsuitable material beneath the existing concrete liner. This resulted in a construction delay and redesign during a critical outage period.

Lesson Learned: As-constructed drawings did not reflect the conditions under the slab and resulted in a significant construction delay. Required field probing, design modifications, and approval from FERC, BOC, and DSOD before the work could progress. Verification of as-builts should be completed in advance of critical schedule work to minimize unforeseen conditions and associated delays.

Iron Gate Diversion Tunnel Anchors



— Iron Gate Diversion Tunnel Cavitation/Venting

Issue: During the initial opening of the existing diversion tunnel gate, significant cavitation noise was observed. Soon after, the newly installed vent pipe in the outlet tunnel failed. This caused significant concern about the level of damage occurring in the tunnel due to cavitation and potential lack of aeration.

Lesson Learned: Though the aeration issue was identified and evaluated in the design, cavitation subsequently occurred and resulted in significant damage to the newly installed vent pipe. Several different options for increasing the air flow to the downstream side of the gate were evaluated, and a design approach used which utilized the easiest access to install the pipe. In hindsight, new vent lines should have been routed down the inside face of the tower to supply the gate where damage due to flowing water would be eliminated.

Iron Gate Diversion Tunnel Cavitation/Venting



From Reservoirs to Rivers: A Look at the Past Year of the Klamath River Renewal Project Restoration Journey

Salmonid Restoration Federation

May 1, 2025



42nd Annual

Salmonid Restoration Conference

Taking the Pulse: Measuring Restoration Success




April 29 - May 2, 2025 Santa Cruz, CA




Restoring a resilient earth
for a modern world

Presenter: Dan Chase
Director, Fisheries and Aquatics

Dams, Tributaries, and Reservoir Footprints



Three Dams – 10 Months



1. Operational Drawdown:

Lowering reservoir to its minimum operating level

2. Initial Drawdown:

Reservoir water evacuation below the Operational Drawdown limits

3. Reservoir Refilling and Releasing Period:

Inflows exceed outflow capacity periodically, causing reservoir levels to rise and fall

4. Dam Demolition:

Reservoir water elevation remains at the top of the historic cofferdam while dam concrete and embankments are removed

5. Klamath River Reconnection:

Breaching of the historic cofferdam, allowing the river to permanently flow in a riverine condition

Copco Dams 2 & 1 – Klamath River – June 2023



Copco Dam 1 – Klamath River – January 2024





Photo: Matt Mais, Yurok Tribe



Photo: Matt Mais, Yurok Tribe

Camp Creek - February 2024



© Copyright 2025 RES

Photo: Sarah Wood, Resource Environmental

Copco Valley - Klamath River - October 2024


Copco Dam 1 - March 2024



Jenny Creek - April 2024



Iron Gate – Klamath River - May 2024



Iron Gate Dam - June 2024



Copco Valley – Klamath River October 2024

JC Boyle Dam Breach - July 2024



Also July 2024... - Iron Gate – Klamath River



Spencer Creek – Klamath River – August 2024



Spencer Creek



July 2024



Spencer Creek



August 2024



Copco 1 Dam - September 2024



JC Boyle – Klamath River - October 2024



JC Boyle – Klamath River - June 2023



JC Boyle – Klamath River - October 2024



Copco Valley – Klamath River - October 2024



Copco Dam 1 and Reservoir - September 2023



Copco Valley – Klamath River - October 2024



Iron Gate Dam Upstream View - January 2024











Former Iron Gate Dam Upstream View - October 2024



Jenny Creek – October 2024






-  10/2 In-water work complete
-  10/1 Pacific lamprey detected in Jenny Creek
-  10/3 first Chinook passed Iron Gate
-  10/15 Chinook detected in Jenny Creek
-  10/16 Chinook detected in Spencer Creek, OR
-  12/5 Coho detected in Beaver Creek
-  12/19 Coho detected spawning in Oregon

Fisheries Monitoring

Primary objective: Inform volitional fish passage through the LKP footprint.

Population monitoring conducted by Yurok Tribe, Karuk Tribe, Klamath Tribes, CDFW, ODFW, NMFS, USFWS, CalTrout, university partners.

- **Fish passage monitoring**
- **Fish presence monitoring – Fall/Winter spawning surveys**
- **eDNA**



Water Quality & Aquatics Program – Data Collection

- Over a dozen regulatory authorizations related to fisheries and aquatics that require an extensive monitoring program



 ***Fish passage monitoring***



Telemetered monitoring location

Restoration Underway in Tributaries and Reservoir Footprints





Sediment Evacuation and Fish Passage
Impediment Removal



Revegetation Efforts



Large Wood Loading







Beaver Creek Valley – Copco Footprint

Photo: John Lang






Seedbed Preparation





Seedbed Preparation at JCB, September 2024 Photo: Nathan McCanne

Tributaries and Reservoir Footprints




Features



Jenny Creek Adaptive Design

JENNY CREEK 2024 VS 2018 CROSS SECTIONS



Adaptive Design Approach

By Improving and then Monitoring:

- Fish Passage
- Bank Stability
- Floodplain Connectivity
- Floodplain Roughness
- Channel Fringe Complexity

Upcoming Restoration Work

2025

- Data collection and field surveys
- Restoration work in priority tributaries
 - Floodplain grading
 - In-channel work
- Fall revegetation effort
- IEV management

Former Iron Gate Reservoir – Klamath River - May 2024



RES Project Partners



Project Contacts

Dave Coffman

Klamath Restoration
Program Manager
dcoffman@res.us

Dan Chase

Lead Fisheries
Biologist
dchase@res.us

Dave Meurer

Director of
Community Affairs
dmeurer@res.us



Thank you!



RES Klamath Story Map



Tributaries and Reservoir Footprints





Spencer Creek

July 2024



Spencer Creek

Aug 2024



Spencer Creek

Aug 2024




Spencer Creek

Jan 2025



Aug 2024



PLAN LEGEND


— 2024 POST-LARGE WOODY MATERIAL THALWEG

SOURCE: BASE MAP IMAGERY FROM DRONE FLIGHT ON AUGUST 12, 2024

40 20 0 40
SCALE IN FEET



Spencer Creek



PROFILE LEGEND

— 2024 POST-LARGE WOODY MATERIAL THALWEG
- - - 2024 POST-LARGE WOODY MATERIAL WATER SURFACE

SCALE: HORIZONTAL 1" = 40'
VERTICAL 1" = 8'

SPENCER CREEK 2024 POST-LARGE
WOODY MATERIAL PLACEMENT
PLANFORM AND LONGITUDINAL
PROFILE

STAMP/SEAL

X



HGS, LLC. A RES COMPANY
2125 19TH STREET, SUITE 200
SACRAMENTO, CA 95818
P: 804.353.6017
WWW.RES.US

© Copyright

Peeshkeesh hûut kích?

Water Quality Conditions During Klamath Dam Removal Drawdown

John R. Oberholzer Dent
Biologist
Karuk Tribe Water Quality Program



Klamath Dam Removal


- 4 dams
- 425 ft. combined height
- 420 miles of spawning habitat upriver
- 4.2 million tons sediment (dry weight) in reservoirs



Drained Copco reservoir



Iron Gate dam (left) and partially drained reservoir during 2024 drawdown



Water Quality Monitoring by Karuk Tribe, Yurok Tribe, USGS, and RES

- 9 continuous monitoring stations (temperature, conductivity, dissolved oxygen, pH, turbidity)
- 14 grab sampling locations (nutrients, sediment, microcystin, heavy metals)
- Other monitoring data not presented here includes continuous monitoring in the reservoir reach (USGS)

KTDNR
WQ Staff



Temporary Impairments

(“Short-term pains”)

- Turbidity/suspended sediment, dissolved oxygen sags, minimal contaminants


Immediate, Long-Term Improvements

(“for long-term gains”)

- Temperature, dissolved oxygen, pH, algal toxins, disturbance, fish disease, fish migration



A year of drawdown: turbidity and DO below the former Iron Gate Dam in 2024



Dam Removal in Perspective: Larger Historic Disturbances


Hydraulic mining during gold rush



Christmas Flood of 1964




2022 McKinney Fire and impacts of catastrophic wildfire (log scale)



Dilution and Improvement of Water Quality Downriver


Dilution of turbidity from storms and geomorphic flow releases (March 2024)



Dilution of suspended sediment concentration samples




Recovery of dissolved oxygen sags (January-February 2024)



The “upside-down” river



USGS, KRIS, NWS



Stillwater Sciences

Dillon Creek dilutes Klamath River, February 27, 2024

Klamath River


Dillon Creek



Klamath River dilutes Trinity River, December 15, 2024

Trinity River

Klamath River



Misinformation about Klamath Dam Removal

~~“river of death”~~

~~“superfund site”~~

~~“collapse of the Klamath River ecosystem”~~

~~“conditions of disaster or extreme peril”~~


Facts about Klamath Dam Removal

- The Klamath River is used for drinking water in only one location, a rest stop on I-5. It was supplied with water by KRRC for the duration of the project.
- Drawdown was timed for winter to avoid recreation impacts as well as salmonid impacts. With winter water temperatures that reach 3 °C, recreation is... limited.
- Volcanic geology creates naturally high background levels of heavy metals.
- Other ongoing water quality concerns (i.e., catastrophic wildfire) have greater long-term impacts.


Fish Mortality

- Nearly 250 overwintering juvenile Coho were rescued from the mainstem Klamath and relocated to off-channel ponds by Tribal and RES staff prior to drawdown
- Some juvenile salmonid and sucker mortality observed during anoxic events caused by initial drawdown (January, extending 40 miles downriver) and cofferdam removal (September, extending 15 miles downriver)
- Hatchery juvenile mortality event was not caused by water quality (still produced more than the scheduled 3.25 million for last year)
- Majority of mortality observed was non-native reservoir fishes (e.g., perch)

Methylmercury before and during drawdown




Methylmercury compared to lowest applicable water quality standard




Total aluminum before and during drawdown (log scale)

*Klamath, Shasta, Scott, and Trinity Rivers are already on the 303(d) list as impaired by aluminum pollution (NCRWQCB)




Modeled max SSC: **~20,000** mg/L vs. actual: **7,290** mg/L (log scale)

Turbidity to SSC regression by USGS



Modeled DO < 7 mg/L: **53** days vs. actual: **6** days



Modeled Expectations vs. Measured Results

Parameter	Modeled	Actual
Maximum SSC (mg/L)	15,000-30,000	7,290
Days above 1,000 mg/L SSC	56	52
Days above 5,000 mg/L SSC	14	4.3
Days below 7 mg/L DO	53	6.2
Days below 5 mg/L DO	12	3.6

2024



2021



2025




Short-Term Drawdown WQ Impacts


- DO sags, including several hours of anoxia, during initial drawdown, cofferdam breach, and cofferdam removal
- SSC below salmonid stress thresholds during 86% of the year
- DO above salmonid stress thresholds during 98% of the year
- SSC and DO impairments much less severe than modeled

What's ahead for a free(-er) Klamath?


Immediate improvements in temperature




Immediate improvements in dissolved oxygen




Immediate improvements in pH



Microcystin samples mostly nondetect in 2024



Increased disturbance in free-flowing reaches (data from USGS)



Before and After June-October Water Quality

% of continuous data below former Iron Gate dam

Parameter	2001-2011 ¹	2012-2023 ²	2024
DO Sat. < 90%	33	62	40
DO Sat. < 85%	22	41	19
pH > 8.5	23	24	<1
pH > 9.0	2	7	0
Temp. > 22 °C	9	1	19

¹ Asarian, E., & Kann, J. 2013. Synthesis of Continuous Water Quality Data for the Lower and Middle Klamath River, 2001-2011. Prepared by Kier Associates and Aquatic Ecosystem Sciences for the Klamath Basin Tribal Water Quality Work Group. 50 pp. + appendices.

² Iron Gate curtain used starting 2015 (water released from lower in the reservoir)

Long-Term Dam Removal Water Quality Improvements

- Lower late summer and fall temperatures
- Higher dissolved oxygen
- Lower and less variable pH
- Almost no microcystin detected
- Restored flow regime and sediment transport regime




Klamath River at Seiad Valley

Water Quality Leads to...

- Reduced fish disease
- Habitat availability, diversity
- Safety for cultural, ceremonial, and recreational use
- Access to healthy traditional foods and other cultural resources
- Healthy communities and economies



Ron & Jason Reed dipnet fishing at Ishi Pishi Falls
(Photo: Noel DiBenedetto)

- 
1. The Klamath River is resilient in the face of dam removal impacts.
 2. Water quality impairments were far less severe than predicted.
 3. Striking water quality improvements are already being realized.



Peeshkeesh hûut kích?

Yêeship!



“MAPPING A NEW RIVER” FIRST SURVEYS OF THE NEW FREE FLOWING KLAMATH RIVER AFTER A CENTURY OF DAMS

**Salmon Restoration Federation (SRF)
May 1st, 2025**



*Yurok Tribe Fisheries Department
Design and Technical Services Program (TSP)
Condor Aviation Program*

*David (DJ) Bandrowski P.E.; Senior Civil Engineer
Cort Pryor; Survey Manager
Geomatics Branch Staff and Fisheries TSP Team*




STANDING ON THE SHOULDERS OF GIANTS... A TRIBUTE TO THE FIGHT



STEWARDSHIP ACROSS THE KLAMATH BASIN – RESTORING BALANCE

THE KLAMATH RIVER IS THE LIFEBLOOD OF THE YUOK TRIBE



THE NEXT GENERATION - CAPACITY BUILDING IN ACTION

RESTORATION ISN'T JUST ABOUT RIVERS... BUT ABOUT PEOPLE



LEARNING FROM THOSE THAT CAME BEFORE US – THE ELWHA



The Elwha River flows into the Strait of Juan de Fuca, carrying sediment once trapped behind dams. The gradual release has rebuilt riverbanks and created estuary habitat for Dungeness crabs, clams, and other species.


PHOTOGRAPH BY ELAINE THOMPSON, ASSOCIATED PRESS

World's Largest Dam Removal Unleashes U.S. River After Century of Electric Production

As Washington State's Elwha River runs free, a habitat for fish and wildlife is restored.

8 MINUTE READ

BY MICHELLE NIJHUIS, FOR NATIONAL GEOGRAPHIC





MAPPING OF THE KLAMATH RIVER (2018)

BASE LINE DATA SET FOR PRE-DAM REMOVAL CONDITIONS

APPROX. 72,000 ACRES; 250 MILES / 400 KILOMETERS

Klamath River Sonar Integration with Topobathymetric LiDAR

Technical Data Report



David (DJ) Bandrowski, P.E.
Senior Project Engineer
Yurok Tribe Fisheries Department
PO Box 1027
Klamath, CA 95548



QSI Corvallis
1100 NE Circle Blvd, Suite 1
Corvallis, OR 97330
PH: 541-752-1204



HOME DATA ▾ RESOURCES ▾ LEARN ▾ ABOUT ▾

Topographic Data Set: Klamath River, California 2018

Welcome David Bandrowski (Sign Out)

Overview

This 2018 Klamath River data set was a multi-agency collaboration to collect pre-dam removal topography and imagery across the rivers 260 mile corridor. Airborne topo-bathymetric LiDAR, boat based multi-beam sonar, and aerial imagery was collected from the mouth at estuary to the head waters near Klamath Lake in Oregon. This comprehensive baseline data set will help inform the scientific and restoration community to more thoroughly understand the effects of dam removal, quantitatively measure sediment transport evolution, and to help monitor the biological and physical response of a new free flowing Klamath River.

- For direct download of ancillary raster products for the Klamath River click here
- For direct download of the orthomosaic for the entire Klamath River click here



Platform: Airborne Lidar
Full Metadata

Survey Area: 291.64 km²
Data Citation

Point Density: 120.39 pts/m²
Use License: Not Provided

Survey Date: 02/11/2018 - 10/07/2018
Funders: USGS, NOAA, hewlett, KRRC
Collectors: QSI, USACE, GMA

Other Available Data Products: Raster (UTM), Raster (SP), Point Cloud Bulk Download

1a. Select area of data to download or process



THE CONDOR AVIATION GEOSPATIAL PROGRAM TAKES FLIGHT

LoCO STAFF / TUESDAY, JUNE 27, 2023 @ 10:01 A.M. / WILDLIFE

Yurok Tribe Acquires Badass, LIDAR-Equipped, Condor-Wing-Bedecked Airplane for Scientific Research and Land Management Purposes



The Yurok Tribe's Cessna Grand Caravan EX aircraft is adorned with condor wings and a traditional basket design. Photo courtesy the tribe's Condor Aviation unit.



DRAWDOWN BEGINS MAPPING A NEW RIVER AFTER A CENTURY OF DAMS AND RESTORING THE HOMELAND OF THE SHASTA INDIAN NATION




AERIAL IMAGERY OF COPCO VALLEY – JANUARY 2024




AERIAL IMAGERY OF COPCO VALLEY – FEBRUARY 2024

- 4 Band Imagery (RGB + NIR)
- Ground Sample Distance Resolution ~ 7-10cm
- Flight Altitude ~ 3,000 ft. AGL




AERIAL IMAGERY OF COPCO VALLEY – APRIL 2024




2024 LIDAR SURVEYS – DEVELOPING DIGITAL TERRAIN MODELS


- Point Density ~ 16pts./m²
(single swath)
- 55% Overlap
- Sensor = Riegl VQ-1560IIS
- Flight Altitude ~ 5000 ft. AGL



PUTTING A NEW RIVER ON THE MAP (*LITERALLY*), DIGITIZING THE KLAMATH AND ITS TRIBUTARIES AFTER MORE THAN A 100 YEARS




GEOSPATIAL ANALYSIS USING 3D MODELING FORM IMAGERY/LIDAR



2025 SATELLITE IMAGERY – PLANET LABS (~1M RESOLUTION)

TASKING DASHBOARD



Mapbox © OpenStreetMap

s106_20250112T2224253Z

1 of 2

INFO

Cloud coverage: 0.4%

Acquired on: 2025-01-12 22:42 UTC

Published to customer: 2025-01-13 03:18 UTC

Order: [Klamath Dam Removal - Iron Gate and Copco - ...](#)

Order type: IMAGE

Scheduling type: FLEXIBLE

Satellite: s106

View angle: 29.00°

[View in Explorer](#) [Copy IDs](#)

EVALUATION

SUCCESS

ID KEYS



Capture	f81c1172-d30f-419e-83e8-20842c30c021
Order	bd2876ea-ea31-448f-9f8d-d9734a29a19f

35 of 35 orders 30.6 km²



BATHYMETRIC MAPPING – BOAT BASED SONAR DATA COLLECTION



DTM COMPARATIVE ANALYSIS 2018 vs. 2024



NEXT STEPS – HOW WILL THE LIDAR AND IMAGERY BE USED: HYDRODYNAMIC MODELS; HABITAT ASSESSMENT; SEDIMENT TRANSPORT; GEOMORPHIC CHANGE DETECTION, MONITORING VEGETATION, ETC.



Water Availability and Use Science Program

Prepared in cooperation with the U.S. Fish and Wildlife Service and the National Fish and Wildlife Foundation

**Sediment Mobility and River Corridor Assessment for a
140-Kilometer Segment of the Main-Stem Klamath River
Below Iron Gate Dam, California**




Open-File Report 2020–1141

U.S. Department of the Interior
U.S. Geological Survey

SUPPORTING TRIBUTARY RESTORATION DESIGNS AND FUTURE PROJECTS ACROSS THE BASIN


TOPOGRAPHIC SURVEY OF COPCO COVE Copco, California




FINAL REPORT • December 2022

Klamath Reservoir Reach Restoration Prioritization Plan

A Summary of Habitat Conditions and Potential Restoration Actions for the Mainstem Klamath River and Tributaries between Iron Gate Dam and Link River Dam



Prepared by:



LOWER KLAMATH PROJECT 90% DRAFT SUBMITTAL



SUPPORTING REVEGETATION OPERATIONS DURING DAM REMOVAL

Seeding and Planting Statistics

7 seed mixes

- 6 mixes were from custom-grown seed

High diversity

- 28 species in total
- 11-20 species per mix

Seed Mix	Lbs Sown	Acres
Rocky Wake Zone	11,128.1	286.0
Wild RWZ*	30.3	-
Grassland-Chaparral	2,769.3	83.5
Oak woodland	1,349.0	70.8
Riparian (low)	102.9	3.0
Ponderosa Pine	1,090.0	30.6
Riparian (high)	175.0	4.3
Native Mix 9	105.0	2.9
TOTALS	16,749.6	481.1

*Supplemented the Rocky Wake Zone mix on 33 acres in Copco only.

- 106,656 plants planted (25 species)
- 320 Oregon white oak acorn clusters (25,585 acorns)
- 39 showy milkweed rhizome clusters (*Asclepias speciosus*/ 1,173 rhizomes)
- 75,898 bare root, container/plug plants



RESTORATION IS ABOUT A RELATIONSHIP TO THE LAND AND THE PEOPLE WHO STEWARD AND ARE THE CARETAKERS



**WHEN THE RIVER IS RESTORED... THE PEOPLE WILL BE HEALED
THE WORK IS JUST BEGINNING...**



Tell me and I'll forget. Show
me, and I may not remember.
Involve me, and I'll understand.

- Native American Saying -

DJ Bandrowski P.E., Senior Project Engineer
Program Manager

djbandrowski@yuroktribe.nsn.us

906-225-9137



THE FIGHT FOR DAM REMOVAL... PROTECTING THEIR EXISTENCE



Copco No. 1 | CA



Copco No. 2 | CA



JC Boyle | OR



Iron Gate | CA

THE KLAMATH - FREEING A RIVER AFTER A CENTURY OF DAMS

IRON GATE



THE KLAMATH - FREEING A RIVER AFTER A CENTURY OF DAMS

COPCO 1





Factors Limiting Filamentous Algae and Rooted Macrophyte Growth During Dam Removal in the Klamath River

Isabelle Tang, *Oregon State University*; Desirée Tullós, *Oregon State University*; Laurel Genzoli, *University of Nevada, Reno*;
Ryan Bellmore, *USFS Pacific Northwest Research Station*; John R. Oberholzer Dent, *Karuk Tribe Department of Natural Resources*

Salmonid Restoration Federation
May 1, 2025

Excessive algae and macrophytes can cause a nuisance in rivers



Filamentous Algae (FA) and rooted aquatic plants (macrophytes) are essential primary producers in a river




Excessive accumulation of FA and macrophyte biomass can be a nuisance and impact dissolved oxygen



Light and discharge are potential limiting factors for growth

Filamentous Algae (FA)



Macrophytes



The factors that drive the growth and senescence of FA and macrophytes are not well understood



A large sediment pulse through the basin was anticipated during reservoir drawdown and deconstruction



The Klamath River has high rates of primary production



Dam removal provided an opportunity to study the impacts of a large sediment pulse on FA and macrophyte growth



Michael Wier / CalTrout




Swiftwater Films

How does FA and macrophyte growth timing, biomass accumulation, and senescence vary with changes in peak discharge, baseflow hydraulics, light availability, and temperature?


(1) Field surveys before and during dam removal

(2) Mechanistic Model

Hypothesis 1: Light controls biomass accumulation.




Hypothesis 2: Discharge controls biomass.



Field Methods






- Macrophytes dominate upriver.
- FA dominates downriver.


Map data: Google, LDEO-Columbia, NSF, NOAA, SIO, U.S. Navy, NGA, GEBCO
 River data: Samantha Adams, U.S. Fish and Wildlife

Data Collection – Field Surveys



- % Cover
- Depth
- Velocity
- Substrate
- PAR
- Turbidity
- Temperature

We converted % cover of FA and macrophytes to Biomass/m²



(Genzoli and Hall in Review)

Field Results



Photo: Sean Nealon

Upriver


Year	Median Summer Turbidity (FNU)*	Spring Peak Flow (cfs)
2023	4	6500
2024	48	3430

Downriver

Year	Median Summer Turbidity (FNU)*	Spring Peak Flow (cfs)
2023	2	34,300
2024	13	51,600

- Median turbidity was higher in 2024 than 2023 at both sites.
- Peak flows were lower at the upriver site, but higher at the downriver site in 2024.

Macrophytes were established much earlier in 2024 than 2023




Upriver Sites

Year	Median Summer Turbidity (FNU)*	Spring Peak Flow (cfs)
2023	4	6500
2024	48	3430

**turbidity data courtesy of the Karuk Tribe*

Max FA biomass was lower and earlier in 2024 than 2023




Downriver Sites

Year	Median Summer Turbidity (FNU)*	Spring Peak Flow (cfs)
2023	2	34,300
2024	13	51,600

**turbidity data courtesy of the Karuk Tribe*

FA and macrophytes persisted in shallow, slow moving water.



Macrophytes overcame low light conditions from sediment pulses.




Photo: Sean Nealon

Algae are more sensitive to light than macrophytes.



Modeling Approach

```
57
58 #FOR LOOP
59 #model run time (days)
60 periods <- seq(0.5,1)
61
62 #set initial conditions fro biomass
63 biomass <- c(5,rep(NA, length(periods)))
64 pscours <- c(0.1,rep(NA, length(periods)))
65
66 df <- data.frame(Period = periods, Biomass=biomass, pscour=pscours,
67                 F1=NA, F2=NA, F3=NA, F4=NA, production=NA, decay=NA, export=NA)
68
69 #i represents the prior period
70 for (i in seq(1,5)) {
71   F1 = ifelse(Temp[i] < Topt, exp(-((Temp[i] - Topt) / (Topt - Tmin / sqrt(log(100))))))
72         exp(-((Temp[i] - Topt) / (Tmax - Topt / sqrt(log(100))))^2))
73   Dcrit = 1000*((z[i]^5)/((rho-1)*tau))
74   pscour = (1/100) * ifelse(Dcrit < 2, fines[i],
75                             ifelse(Dcrit >= 2 & Dcrit < 64, gravel[i] = fines[i],
76                                   ifelse(Dcrit >= 64 & Dcrit < 257, cobble[i] = gravel[i],
77                                         ifelse(Dcrit >= 257, boulder[i] = cobble[i]
78
79   F2 = 1 - ((dfsBiomass[i])/(dfsBiomass[i] + (1-pscour)*kb))
80   F3 = PARbed[i]/(PARbed[i] + kpar)
81   F4 = pmin(1, 0.2 + abs(v[i])/(abs(v[i])+kv))
82   production = dfsBiomass[i] * gmax * F1 * F2 * F3 * F4
83   decay = dfsBiomass[i]*dref*tc^(Temp[i] - Tref)
84   A = z[i]^0.4
85   P = 2*z[i]+ 0.4
86   R = A/P
87 }
```

Environment History Connections Tutorial


Import Dataset 418 MB

R Global Environment

	0.004
	0.045
	1.08
num [1:5]	17 18 22 23 20
	30
	-10
Topt	20
Tref	20
u	0.0511468474101777

Files Plots Packages Help Viewer Presentation

Biomass over Time




Console Terminal Background Jobs


```
R 4.3.2 - C:/Users/tangh/Box/Thesis/Model/Toy Model/
+ TRIM$X$Y$Z = BIOMASS OVER TIME
+ x = "Day",
+ y = "Biomass (g AFDM m-2)" +
+ theme_minimal()
```


Mechanistic Simulation Model

$$\frac{\Delta \text{Biomass}}{\Delta \text{time}} = \text{production}_i - \text{decay}_i - \text{export}_i$$




Data were clustered based on depth and velocity.




Modeling Results




Macrophyte dynamics can be roughly reproduced by discharge, light, and temperature



Potential improvement: Incorporate species dynamics



Algae dynamics are likely more complex than the model processes.



Potential improvement: Incorporate limitation via self shading





Future Work

Summer 2025 Field Surveys

+ Data, Update Model
Processes

Thank you!

- Co-Authors
- Field Crew
 - Lily Bell
 - Emelyn Keller
 - Kristine Alford
 - Rebecca Wheaton
 - Grace Boisen
 - Whitney Packard
- Yurok Tribal interns
- John Bolte
- Ciana David
- Karuk Tribe Water Quality Department


Questions or comments?

Email: tangis@oregonstate.edu



Oregon State
University

Macrophytes persisted in shallower, slower moving water.



Macrophyte Model Parameters and Results

Cluster	Habitat Type	Growth Rate (gmax)	Decay Rate (dref)	Decay Shape Coeff (ai)	Density Half Saturation (kb)	PAR Half Saturation (kpar)	Velocity Half Saturation (kv)	RMSE - Train (g AFDM/m ²)	RMSE - Test (g AFDM/m ²)
1	Shallow, Low Velocity	0.20	0.01	5.00	7.15	2.50	0.14	0.14	3.00
2	Deep, Low Velocity	0.20	0.09	10.00	3.00	5.00	0.18	0.07	8.50
3	Mod Depth, High Velocity	0.20	0.01	9.87	3.35	2.50	0.15	0.50	1.55

Algae Model Parameters and Results

Cluster	Habitat Type	Growth Rate (gmax)	Decay Rate (dref)	Decay Shape Coeff (ai)	Density Half Saturation (kb)	PAR Half Saturation (kpar)	Velocity Half Saturation (kv)	RMSE - Train (g AFDM/m ²)	RMSE - Test (g AFDM/m ²)
1	Shallow, Low Velocity	0.55	0.12	10.38	3.61	9.00	0.14	0.63	1.23
2	Deep, Low Velocity	0.36	0.12	9.96	2.55	2.50	0.14	0.31	0.25
3	Mod Depth, High Velocity	0.35	0.12	15.00	1.00	9.00	0.15	0.21	0.09

Macrophytes and FA occupy specific depth and velocity habitat ranges.

Macrophytes are driven by discharge and can ~~adapt~~ overcome ~~to~~ low light.

Filamentous algae is more sensitive and less adaptable to low light ~~but more~~
robust ~~to independent~~-peak flows.

Macrophyte dynamics can be roughly reproduced with peak flow, baseflow hydraulics, light availability, and temperature.

Algae dynamics are more complex than the processes represented in the model.

Quantifying short-term food web responses to dam removal on the Klamath River




Rosa Cox
Dr. Alison O'Dowd
Toz Soto



INTRODUCTION:

Dam Removal – short term impacts

- 3 million metric tons of sediment stored behind the dams in 3 reservoirs
- 84% fines (silts and clays)
 - expected to mobilize and move rapidly downstream
 - Potential direct and indirect impacts to juvenile salmonids (and other fish)






Food webs and benthic macroinvertebrates

- Benthic macroinvertebrates (BMI):
 - High quality fish food
 - Indicators of stream quality/ecosystem health

Elwha dam removal: lessons learned

Spring Drift Samples:

- Decline in invertebrate drift during 2 years of dam removal in mainstem between and below dams (LME)



Elwha drift energy densities (J/m^3) by terrestrial vs aquatic origin in sections sections below the dams (LME) with reference sites in Tributaries (TR). Adapted from Morley et al. 2020

Mechanisms for potential impacts from reservoir sediments:

High Suspended Solids Concentration (SSC)


- Low Dissolved Oxygen
- Physical damage:
 - gill/gut clogging
 - abrasion of gills/tissue
- Exposure to toxins/heavy metals**
- Reduced primary productivity resulting from lower light infiltration
- (+) nutrient subsidies


Sediment deposition

- Direct burial
- Loss of habitat in interstitial spaces
- (+) increased habitat for sediment – burrowing taxa



STUDY DESIGN:






Sites:
paired mainstem
and tributary

BEFORE
2022 = 4 sites (pilot)
2023 = 8 sites

DURING
2024 = 8 sites

Sampling Methods



2. Drift (30 min drift)

3. Juvenile salmonid diet (gastric lavage)




1. Benthic (1min kick)

Sampling Season


SPRING:

- All sample types and sites
- May-June 2022-2024




FALL:


- Benthic samples only
- fewer sites
- November 2023 & 2024



Sampling design



Site-specific sampling



Laboratory methods




Benthic:

- Aquatic insects identified to genus*


*non-insects = class/order

*terrestrial insects = order



Drift and Diet:

- Aquatic insects identified to family*
- Length measured to nearest mm
 - Biomass estimated using taxonomic specific length-weight regression



203,468 individuals identified and enumerated



(Preliminary) Data Analysis

- Linear mixed effect models
 - Log-transformed responses (counts, biomass, gut fullness)
- 2-way ANOVA, Tukey HSD pairwise comparisons
- $\log(Y_i) = \beta_0 + \beta_1(\text{SiteType}_i) + \beta_2(\text{Treatment}_i) + \beta_3(\text{Treatment}_i * \text{SiteType}_i) + \alpha_{\text{site}[i]}$

$$\alpha_{\text{site}[i]} \sim \text{Norm}(0, \sigma_{\text{site}}^2)$$






RESULTS

DRIFT:

No significant shifts in **biomass density (mg/m³)** or **abundance (counts)**




DIET :

Significant increase in total abundance and biomass
(gut fullness)



Site	year	# samples	# empty stomachs
KL_BB	2023	19	10
KL_BB	2024	23	1
KL_GT	2022	20	4
KL_GT	2023	20	8
KL_GT	2024	20	0




DIET :

Taxonomically diverse,
no clear winners

DIET :


Taxonomically diverse,
no clear winners



BENTHIC:

No change in abundance
between **Spring** samples

Abundance declined
significantly in
2024 Fall





BENTHIC (SPRING):

Shannon diversity declined at
2 sites closest to Iron Gate Dam



BENTHIC (FALL):


Shannon diversity declined only at
Iron Gate



Initial drawdown vs coffer dam removal




Drawdown and coffer dam removal sediment pulses



Continuous water quality data from RES


McKinney Fire sediment pulses



Continuous water quality
data from RES

Already lots of extra sediment in the river

- McKinney Fire between 2022 and 2023 sampling seasons



McKinney fire sediment



Discharge
(CFS)

Klamath R NR Seiad Valley CA - 11520500


November 7, 2022 - November 7, 2023

Discharge, cubic feet per second

1670 ft³/s - Aug 22, 2023 03:30:00 AM PDT




Temp C




Take homes:

- Dam removal didn't cause dramatic changes in SPRING juvenile salmonid diet availability
- Timing of sediment flushes (relative to flow in the river and water temperature) may be important for mitigating impacts



Next steps:

- GLMM in Bayesian framework
 - Spatial trends (distance from dam)
 - Parse out McKinney Fire vs dam removal?
- Multivariate community analyses
- Taxonomic variability in response
 - Who is driving the decline in diversity?
- Monitor future trends
 - Next graduate student



Acknowledgements


- **Thesis committee:** Dr. Alison O'Dowd, Dr. Nicholas Som, Dr. Darren Ward
- **Karuk Tribe Fisheries:** Toz Soto, Clayton Tuttle, Ben Harrison, Aaron Tuttle
- **O'Dowd Lab:** Elizabeth Uemura, King Baptista, Amanda Podkomorka, Michael Paige, Kelly Corcoran, Andre Giraldi, Theo Murphy, Blake Gonzales, Victoria Budke, Ben King, Julia Nehl
- **U.C. Davis Lusardi lab:** Rob Lusardi, Brandi Goss, Sarah Howe






Questions?

Drift Biomass (no zooplankton)




DRIFT:

No significant change in
proportion of terrestrial vs.
aquatic origin




DIET :


No significant change in
proportion of terrestrial vs.
aquatic origin





Proportion of Terrestrial vs. Aquatic Origin, Gut fullness (mg/g)



Diet site specific shifts in terr v aquatic




BENTHIC community shifts – fall v spring for each sitetype/year




Klamath expectations: shifts in fish diet availability


Before sediment pulse



During sediment pulse




WQ (RES data)



Reservoir Drawdown

Coffer dam removal




Reservoir Drawdown

Coffer dam removal

Elwha dam removal: lessons learned

Spring (May – June)

Summer (July – August)



Elwha drift energy densities by terrestrial vs aquatic origin in sections between dams (ME) and below dams (LE), with reference sites in Tributaries (TR). Adapted from Morley et al. 2020



Klamath River Effectiveness Monitoring

Alex Corum
James Whelan

SRF 2025

Photo by Michael Weir

AFTER



BEFORE



Klamath Basin

Current and Potential Anadromy


- ★ Project Dam
- Non-Project Dam (with fishway)
- Other Major Dam

- Upper Klamath - estimated Pacific lamprey potential (beyond salmonid potential)

--- State Boundary





Area without potential anadromy



Reach Type

- Lower Klamath - current and estimated potential anadromy
- Upper Klamath - estimated potential anadromy (UKB Reintroduction Plan DRAFT)





Phase 1 Monitoring



- • **How Many?**– SONAR below Iron Gate
- • **What Species?** Tangle netting for species apportionment
- • **Where are they going?** Radio telemetry tagging fish at tangle net sites and stationary and mobile tracking.

**July 15th,
2024**

Kickoff Meeting

**October 4th,
2024**

First Fish Detected
by SONAR

**October
22nd, 2024**

First Chinook
Caught and
Tagged

**September
9th, 2024**

Initial SONAR
Deployment

**October
16th, 2024**

First Tangle
Netting

**December
4th, 2024**

First Coho Caught
and Tagged

Monitoring Strategies

SONAR



Tangle Netting



Radio Telemetry




SONAR: ARIS Camera



- Deployed just downstream of the IGD footprint
- Sound waves deploy to show pyramidal cross-section
- Deployed in Sep/Oct, 2024
- Records 24/7

SONAR: ARIS Camera




○ Deployed just downstream of the IGD footprint

○ Sound waves deploy to show pyramidal cross-section

○ Deployed in Sep/Oct, 2024

○ Records 24/7

Length Histogram from SONAR (10/17/2024 to 11/12/2024)



Tangle Netting



- Kick-off effort Oct 16th
- Safely capture and secure fish for tagging
- Physical samples taken for genetics and aging
- Each fish dual tagged with Radio and PIT tags

Tangle Netting



- Kick-off effort Oct 16th
- Safely capture and secure fish for tagging
- Physical samples taken for genetics and aging
- Each fish dual tagged with Radio and PIT tags

Capture Summary



- Weeks Netted Up to 1/30/2025
 - 10
- Weeks with Fish Caught up to 1/30/2025
 - 8
- Total Fish Caught up until 1/30/2025
 - 20
- Total Chinook Caught up until 1/30/2025
 - 4
- Total Coho Caught up until 1/30/2025
 - 2
- Total ~~Steelhead O. mykiss~~ Sáap caught up until 1/30/2025
 - 14

Radio Telemetry



- Tags deployed externally
- Archival and environmental tags
- Secured to all three species
- Mobile tracked and stationary arrays

Radio Telemetry



- Tags deployed externally
- Archival and environmental tags
- Secured to all three species
- Mobile tracked and stationary arrays

Radio Telemetry



- Tags deployed externally
- Archival and environmental tags
- Secured to all three species
- Mobile tracked and stationary arrays



Thank you

